FIP/P1-10; H. Tobari et al., (QST, Japan)




Completion of DC 1 MV power supply system for ITER neutral beam test facility



Manufacturing and installation of DC 1 MV power supply for ITER NBTF has been completed.

DC 1 MV Power Supply for ITER NBI 1 MV, 60 A for 3600 s

Established by combining several DC 1MV insulation technologies














- The first trial of the high-voltage test on the assembled components started.
- •For a risk mitigation, high-voltage was applied to each section.
- •As an initial test, the HV test on DCG and DCF was examined, and <u>DC 1.2 MV</u> <u>was successfully sustained for 1 hour</u> w/o breakdown.

