

# Regulatory Control Features and Principles for a Land-Based RITM-200N SNPP Project

International Conference on Small Modular Reactors and their Applications

#### **Dmitry V. Shchekin**

Deputy Chief Designer of PWR Plants for Small-Sized NPPs

#### laroslav O. Bykh

Head of the Group for Project Organizational and Technical Support

#### Inna V. Yurina

Design Engineer

### **Paper Purpose and Structure**



2

#### **Purpose**

#### Paper structure

Inform the workshop attendees on the progress of the RITM-200N-based first-of-a-kind small-sized nuclear power plant project in the Republic of Sakha (Yakutia) and on the status of activities being done to take into account in the land-based SNPP\* project the requirements of Russian and international standards and regulations

- 1. RITM-200N-based FOAK\*\* land-based SNPP Project Characteristics and Status
- 2. Key Engineering Solutions in the RITM-200N Reactor Plant
- 3. RITM-200N Reactor Plant Main Equipment
- 4. Safety Concept
- 5. Approaches to Regulatory Assurance for the RITM-200N Project
- 6. Activities to Take into Account in the land-based SNPP Project the Requirements and Recommendations of International Standards and Regulations
- 7. Conclusion

<sup>\*</sup> SNPP – small nuclear power plant

## Caused by land-based SNPP\* Project Implementation, the Effects on the Socio-Economic Development of Remote and Isolated Areas



#### Reduced fossil fuel costs

The replacement of current dieseland coal-fueled facilities will **reduce** annual costs of expensive externally sourced hydrocarbon fuel

#### **Energy security of the region**

Fuel has to be supplied to the landbased SNPP once every 5–6 years

#### Reduced electricity rates

The remote region will be provided with an economically efficient and reliable modern energy source

#### **Creation of new job vacancies**

The land-based SNPP construction creates new **jobs**, **especially** in the peak construction period

### **RITM Reactor Plants**









2020, the Multipurpose Nuclear-Powered Icebreaker (MNPI) Arktika commissioned

2021, the MNPI Sibir commissioned

2022, the MNPI Ural commissioned

2024, the MNPI Yakutiya to be commissioned

Name	RITM-200	RITM-200S	RITM-200N	RITM-200M	RITM-400	RITM-400M
Reactor plant (RP) power, MW	2×175	2×198	1×190	2×198	2×315	2×340
Design lifetime, h	320,000	340,000	495,000	480,000	320,000	340,000
Weight, t	2,200 (2 RPs)	2,300 (2 RPs)	1,500 (1 RP)	2,600 (2 RPs)	3,893 (2 RPs)	4,560 (2 RPs)
Overall dimensions, m	6×13.2×15.5	6.0×13.2×15.36	Ø8.7×21	6.8×14.6×16	9×18.2×17.5	20.76×8.4×18.0

## RITM-200N-Based FOAK\* land-based SNPP\*\* Project Characteristics and Status



Electric power, MW, gross:	55 30 (0.12)	
Station area, acres (km²)		
Refueling interval, year	6	
Service life, year	60	
Load follow operation in the power range, % of rated power	20–100	
Steady-state availability factor over the	over 0 0	





### **PROJECT STATUS**

reactor plant service life

2019, technical and economic studies completed for the land-based SNPP construction in Yakutia

2020, the DOI\*\*\* approved for the construction of RITM-200N-based land-based SNPP in Yakutia

**2021**, materials developed for justification of investments for the construction of the RITM-200N-based land-based

SNPP in Yakutia

**2022**, a detailed design developed for the RITM-200N reactor plant

**2022**, a detailed design developed for the reactor core

2023, a siting license obtained for a nuclear plant for the facility titled Yakutia land-based SNPP Unit No. 1 (Ust-Kuiga village)

over 0.9

2023, a detailed design developed for a nuclear fuel handling equipment complex

2024, decision is made to switch to two-unit version

\* FOAK - first-of-a-kind


\*\* SNPP – small nuclear power plant

\*\*\* DOI – Declaration of Intentions

## RITM-200N-based land-based SNPP General Layout Diagram




#### 55 MWe Yakutia land-based SNPP



- 1, Reactor unit
- 2, Special unit
- 3, Turbine unit
- 4, Electric unit
- 5, Administrative and household building
- 6, Auxiliary building
- 7, Dry sectional cooling tower
- 8, Radwaste container storage point


#### 110 MWe land-based SNPP

40 acres (0.16 km<sup>2</sup>)



#### 220 MWe land-based SNPP


220 MW, 67 acres (0.27 km<sup>2</sup>)



#### 330 MWe land-based SNPP

Ust-Kuiga village

330 MW, 94 acres (0.38 km<sup>2</sup>)



## **Proven and Unified Engineering Solutions** for RITM-200-Type Reactor Plants





Steam generator cassette



Reactor vessel installed in a special slipway



Fuel handling process



steam generating unit




Transporting the RITM-200 steam generating unit



Icebreakers Arktika, Sibir and Ural

## **Key Engineering Solutions in the RITM-200N Reactor Plant**






- integral water-cooled water-moderated reactor
- once-through steam generator
- canned reactor coolant pump
- reactor plant main equipment inside a steel containment
- external gas pressurizer system
- purification and cooldown system (PCDS), a normal operation system and a safety system
- electromechanical reactivity control system; no boron control
- self-sustaining ammonia water chemistry
- operational power variation range from 20 to 100%
- refueling with the use of containers and the central hall crane


### **RITM-200N** Reactor Plant Main Equipment



#### **Reactor Plant Biological Shielding**




#### **Reactor Plant Main Equipment**



The purpose of the development is to create, for the pilot land-based SNPP, the RITM-200N reactor plant that would be based upon marine reactor plant mature engineering solutions verified by experience in design, manufacture and operation, and that would meet modern safety requirements for nuclear power plants

## RITM-200N Integral Reactor with the AS-14-15 Core Comprised of an Array of Fuel Assemblies, for the land-based





#### Integral reactor

Manufactured in series. 8 RITM-200 reactor plants have been installed in 4 MNPIs *Arktika*, *Sibir*, *Ural and Yakutiya Arktika*, *Sibir* and *Ural* have been commissioned

#### Reactor pressure vessel

Assigned service life: **60** years Assigned lifetime: **495,000** h

#### SG cassette

Assigned service life: **20** years Assigned lifetime: **165,000** h

#### **RCP**

Assigned service life: **20** years Assigned lifetime: **165,000** h

#### **CG** and safety rod drives


Assigned service life: **20** years Assigned lifetime: **165,000** h

#### AS-14-15 reactor core

The analogs are cores comprised of an array of fuel assemblies:

- 14-15-1 for the RITM-200 reactor plant (MNPIs)
- 14-14 for the KLT-40S reactor plant

(FPU Akademik Lomonosov)



Fuel type: cermet fuel enriched to below 20%

## **Safety Concept**



## Preventing abnormal operation

Assessing and selecting the site, developing the design on the basis of a conservative approach; quality assurance; using proven engineering solutions; well-developed plant inherent safety features (negative reactivity feedbacks, integral reactor layout, high heat storage capacity of the primary system, etc.).

## Preventing design-basis accidents

**Timely detecting deviations** from normal operation and eliminating the deviations; control in operation with deviations (structure and algorithms of control systems, redundancy of normal operation equipment).

#### Preventing beyonddesign-basis accidents

**Using safety systems** that perform control, protection, confinement and safety functions and that prevent initial events from escalating into design-basis accidents; and design-basis accidents, from escalating into beyond-design-basis accidents. **Ensuring passive core cooling in a complete blackout:** 

- ✓ with a leak-tight loop, for an unlimited time
- ✓ in LOCAs, for at least 72 hours

#### Beyond-designbasis accident management

Preventing the escalation of beyond-design-basis accidents and mitigating their consequences with the use of special engineered features for beyond-design-basis accident management (an emergency core cooling system with hydraulic accumulators, a passive residual heat removal system, pressure-actuated circuit breakers), as well as any systems and elements capable of performing the required functions under the existing conditions.

Protecting the reactor plant leak-tight enclosure against destruction and maintaining the enclosure operability (retaining the corium within the reactor pressure vessel, excluding criticality in the course of melting, excluding hydrogen formation, relieving the containment emergency pressure).

#### SAFETY CRITERIA AND TARGETS

- buffer area within the land-based SNPP site limits;
- radiation exposure for the population during normal operation: less than **0.01**% of the natural background radiation;
- total probability of severe accidents for the reactor plant: below 10-6 at an interval of 1 year;
- total probability of severe accidents for the reactor plant: below 10-5 at an interval of 1 year;
- total probability of a major accidental release for the land-based SNPP: below 10-7 at an interval of 1 year.

## **Approaches to Regulatory Assurance of Safety for the RITM-200N Project**





The RITM-200N-based land-based SNPP project is being developed in compliance with the applicable federal standards and regulations in the field of nuclear energy use for nuclear power plants.



As part of developing the reactor plant detailed design, the Analysis of land-based SNPP Nonconformities with the Requirements of the Applicable Regulatory Documentation in the Field of Nuclear Energy Use as Regards the RITM-200N Reactor Plant was formalized. The final design for the RITM-200N reactor plant was completed in June of 2022.



The land-based SNPP project materials provide information on justifications and measures adopted in the project to compensate for deviations from regulatory documentation requirements for NPPs of the Russian Federation.



The work is in progress to take into account, in the land-based SNPP project incorporating the RITM-200N reactor plant, the requirements and recommendations of international standards and regulations.

## Activities to Take into Account in the land-based SNPP Project the Requirements and Recommendations of International Standards and Regulations (1/3)



### SECTION 1. Analysis results for IAEA, EUR, ASME regulatory documentation (2020–2022)

## Radiological criteria for dose rates for the personnel and population

SP AS-03, NRB-99/2009 SSR-2/1 (rev.1), SSG-2 (rev.1), GSR Part 3. EUR (rev. E) It has been identified that the requirements in the regulatory and legal documents on safety of Russian nuclear plants are analogous to the IAEA requirements or propose the same approaches to the implementation of the design requirements.

#### Safety analysis requirements

SF-1, GSR Part 4 (Rev.1), SSR-2/1 (Rev. 1), SSR-2/2 (Rev. 1)

The IAEA requirements for a deterministic safety analysis are largely concur with similar requirements in the Russian regulatory documents.

In the vast majority of cases, the probabilistic safety analysis requirements coincide in the Russian regulatory documents and in the IAEA regulatory documents.

The work is planned to harmonize the Russian deterministic analysis methodologies and the recommendations in the IAEA regulatory documents.

## Strength analysis requirements for equipment and systems

ASME Boiler and Pressure Vessel Code, Section III—Rules for Construction of Nuclear Facility Components—Division 1 (2015)

The basic requirements in the Russian Standards used for strength analysis are in a majority of cases more stringent than those in the ASME Code.

In individual cases, the ASME Code has more conservative requirements than those in the Russian regulatory documents. For certification under the ASME Code, project design documentation may have to be slightly reworked, in a number of cases, without changing design and schematic solutions in the project.

## Activities to Take into Account in the land-based SNPP Project the Requirements and Recommendations of International Standards and Regulations (2/3)



#### SECTION 2. Work results of the IAEA Working Group "Review of Applicability of Safety Standards to Novel Advanced Reactors" (2020–2021)



The IAEA SSG-52, SSG-56, SSG-63 guides were analyzed. The results of the analyses were provided to the IAEA.

DOCUMENT	FUNDAMENTAL DIFFERENCES			
SSG-56 "Design of the Reactor Coolant System and Associated Systems for Nuclear Power Plants"	There is no boron control system, and there are no requirements to continuously monitor the boron solution concentration in the reactor and in the reactor coolant system.  A vertical once-through steam generator is used that is placed in the reactor pressure vessel.  In the regions that require the reactor to be completely disassembled, the reactor pressure vessel inspection and testing periodicit (for non-destructive testing and destructive testing of witness samples) is tied to the mid-life repair dates.  The steam generator design does not allow steam generator tubes to be inspected in the course of operation. Nevertheless continuous parametric monitoring of the SG cassette integrity is ensured. A quick detection of microleaks with rapid localization has been ensured.			
SSG-52 "Design of the Reactor Core for Nuclear Power Plants"	It is not provided for that there be any partial refuelings, variations of loading patterns and off-design core modifications. Boron dissolved in the coolant is not used to control reactivity in the RITM-200N-based land-based SNPP project. Fuel pellets are not used in the RITM-200N-based land-based SNPP project. The fuel matrix has a strong metallurgical bond with the cladding; there is no free volume under the cladding.			
SSG-63 "Design of Fuel Handling and Storage Systems for Nuclear Power Plants"	Uncertainties associated with reshuffling partially burned fuel assemblies are excluded.  Off-design core modifications are excluded.  There are no partial refuelings in the reactor plant. Fuel assemblies are discharged after the design stored energy has been exhausted.  The RITM-200N reactor plant design features rule out a possibility of using a refueling machine for fuel handling.  As a reference solution for the nuclear fuel handling system, a process is used in the land-based SNPP project that employs a transfer container to transport the fuel from the reactor to the spent fuel storage.			

## Activities to Take into Account in the land-based SNPP Project the Requirements and Recommendations of International Standards and Regulations (3/3)



SECTION 3. Results of activities performed under the ROSATOM's Implementation Plan (2022–2023)

 $\bigcirc$ 

The Thematic Working Group of specialists from Afrikantov OKBM and GSPI JSC has developed proposals for the research work report on the "Analysis of the IAEA safety standards to determine the need to develop new IAEA documents and/or make changes to the existing ones, taking into account the land-based SNPP features"—the proposals to be eventually sent to the IAEA.

For 2023, the work is planned to develop proposals for harmonizing the Russian federal standards and regulations in the field of nuclear energy use with the IAEA standards as regards the land-based SNPP and innovative reactors.

## Proposals to Develop New IAEA Documents and/or Make Modifications to the Existing Documents with Account of land-based SNPP Features

- Taking into account the RITM-200N reactor core features, develop an IAEA safety guide titled "Design of the Dispersion Fuel Reactor Core for Small-Sized Nuclear Power Plants" (an **SSG-52 analogue**).
- Taking into account the nuclear fuel handling features (the fuel is moved in air in a special shielded container), develop an IAEA specific safety guide titled "Design of Fuel Handling and Storage Systems for Small-Sized Nuclear Power Plants" (an SSG-63 analogue)
- Add to Section 3.115 of the SSG-56 Safety Guide the following provision: "If it is impossible to inspect tubes in a compact SG, it is necessary to ensure continuous parametric monitoring of SG tube leak-tightness in the course of operation and the possibility of localizing the leaking SG without shutting down the reactor."

### Conclusion





The activities completed for the land-based RITM-200N SNPP have verified that it was a correct strategic decision to use the multipurpose nuclear-powered icebreaker RITM-200 reactor plant type in the small-sized nuclear power plant for the specified power range.



It is noted that there is prospective demand for modular-type land-based SNPPs equipped with the RITM-200N reactor plants due to the economic features of the land-based SNPPs.



The land-based RITM-200N SNPP project is being developed in compliance with the applicable Russian regulatory documentation in the field of nuclear energy use for nuclear power plants.



The analysis of the requirements in the Russian regulatory documentation and in the IAEA Safety Standards, as well as the analysis of the WENRA and EUR requirements has shown that the requirements in Russian regulatory documents are mainly harmonized with modern approaches and requirements used outside Russia. There is no need to develop new IAEA upper-level documents (SF, GSR, SSR). The assessment of the IAEA Guides (SSGs) in terms of their applicability for the land-based SNPP project has shown that the existing IAEA Guides (SSGs) can be updated or new ones to be developed.

# Thank you for your attention

**Dmitry V. Shchekin** 

Deputy Chief Designer of PWR Plants for Small-Sized NPPs

laroslav O. Bykh

Head of the Group for Project Organizational and Technical Support

Inna V. Yurina

**Design Engineer** 

E-mail: okbm@okbm.nnov.ru

www.okbm.nnov.ru