




irfm




# Operating the WEST Superconducting Long Pulse Tokamak

V. Lamaison, E. Corbel, A. Ekedahl, L. Gargiulo,  
S. Hacquin, M. Houry, P. Moreau, L. Toulouse  
and the WEST Team



# OUTLINE

- 1. Introduction on WEST Superconducting Tokamak & Ancillary Systems**
- 2. WEST Achievements, Operation, Availability since December 2022**
- 3. Two Highlights specific to Long Pulse Operation Tokamak**
  - Infrared protection for plasma facing components**
  - Actively Cooled Components & Water Leaks management**



# **1 ■ Introduction on WEST Superconducting Tokamak and Ancillary Systems**



# WEST: a MA class superconducting tokamak



- ❑ Full tungsten actively cooled environment
- ❑ Flexible magnetic configuration (LSN, USN, DN)
- ❑ Large current drive capability
- ❑ **Long pulse operation → 1000 s**

|                         |                                    |
|-------------------------|------------------------------------|
| $I_p (q_{95} \sim 2.5)$ | 1.0 MA                             |
| $B_\phi$                | 3.7 T                              |
| R                       | 2.5 m                              |
| a                       | 0.5 m                              |
| A                       | 5-6                                |
| Max $\kappa$            | 1.35                               |
| $\delta$                | Up to 0.5                          |
| $V_p$                   | 15 m <sup>3</sup>                  |
| $n_{GW} (1MA)$          | $1.5 \cdot 10^{20} \text{ m}^{-3}$ |
| $P_{ICRH}$              | 9 MW                               |
| $P_{LHCD}$              | 7 MW                               |
| $P_{ECRH}$              | 3 MW<br>(2024 - 2025)              |
| $T_{flattop}$           | 1000 s                             |

# WEST: a Tungsten divertor, superconducting & actively cooled tokamak



| Phase 1 (Dec 2016 – Jan. 2021)                        | Phase 2 ( $\geq 2021$ )  |
|---|--|
| Actively cooled + W coated inertial divertor elements | <b>Completely actively cooled ITER grade divertor prototypes and baffles</b> |

# WEST Ancillary Systems

## ❑ Magnetic system

- 18 TF Superconducting NbTi magnets (160 tons), Thermal Shields (20 tons)
- 9 CS/PF water cooled Copper Coils
- Upper and Lower water cooled Copper Divertor Coils

## ❑ Cryoplant to cool down magnets

- 3kW @ 4.5K (1/3 of JT-60SA cryogenic system)
- 3.5 tons of helium inventory
- Gas helium (200 bar) and Liquid helium storage

## ❑ Water cooling system to remove heat loads from Plasma Facing Components (PFC) and continuous systems



- 15MW (upgrade of additional 5MW for 1000s plasma)
- Dedicated high pressure and temperature water loop

## ❑ Electrical Power Supplies

- 400kV: Pulsed power Electrical Network
- 2 x 15kV: Steady state Electrical Network

## ❑ Heating systems

- Lower Hybrid: 7MW, 1000s
- ICRH: 9MW, 30s; 3MW, 1000s
- ECRH: 3MW, 1000s



400kV



2 x 15kV



# **2 ■ WEST Achievements, Operation, Availability since December 2022**

# Main achievements since December 2022



## C6&C7 plasma campaigns

Dec. 2022-April 2023

- 3.5 months
- 5h30 plasma cumulated duration**
- 44GJ injected energy
- Max Lower hybrid 5MW, max ICRH 4MW
- 100s plasma pulses



## C8&C9 plasma campaigns

Dec. 2023-April 2024

- 4 months
- 5h45 plasma cumulated duration**
- 38GJ injected energy
- Max Lower hybrid 5.8MW, max ICRH 4.5MW
- Plasma pulse > 6min achieved**

## Plasma pulses

| Plasma pulses    | Total | Failed | Commissioning plasmas | Physics program |
|------------------|-------|--------|-----------------------|-----------------|
| <b>C6&amp;C7</b> | 1420  | 13%    | 15%                   | <b>72%</b>      |
| <b>C8&amp;C9</b> | 1478  | 9%     | 14%                   | <b>77%</b>      |



- 30 pulses/day (shift up to 9:00pm)
- 22 pulses/day (shift up to 6:00pm)



# WEST Operation



## Yearly operation target

- 2 campaigns of ~3 months
- Shutdown for maintenance and evolutions of 4.5-5 months
- Commissioning of 1 month before campaign


## Week operation

- Monday dedicated to Maintenance/Boronisation
- 4 operation days in two shifts  
(2 days 8:45am-6:00 pm + 2 days 8:45am-9:00pm)


| 2023 |     |     |     |     |     |     |     |     |     |     |     | 2024 |     |     |     |     |     |     |     |     |     |     |     |
|------|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|------|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|
| Jan  | Feb | Mar | Apr | May | Jun | Jul | Aug | Sep | Oct | Nov | Dec | Jan  | Feb | Mar | Apr | May | Jun | Jul | Aug | Sep | Oct | Nov | Dec |
| S6   | C7  |     |     | S7  |     |     |     |     |     |     | C8  | S8   | C9  |     |     | S9  |     |     |     |     |     |     | C10 |

- **WEST availability > 70% since 2019** during plasma campaigns
- Shutdown and commissioning phases longer than expected


$$\text{Availability} = \frac{[\text{session duration achieved}] - \text{downtimes duration}}{[\text{session duration expected}]}$$



Expected



Performed



■ Campaign days ■ Shutdown days ■ Commissioning days


■ Campaign days ■ Shutdown days ■ Commissioning days



# Commissioning before campaign

After Shutdown, commissioning duration is about 1 month:

- **Cool-down of the magnets**
- Helium leak detection on vacuum vessel
- **Water Cooling loop filling (30m<sup>3</sup>), High-pressure leak test, Chemical Treatment of water**
- Baking at [200°C, 35bar] of the vacuum vessel



Magnets cool down  
~ 3 weeks from  
300K to 1.8K

→ Incident on cryogenic system results in a long time delay (~ 2months) for plasma operation mostly due to warm-up and cool down of the magnets

~ 4 weeks  
from Tokamak  
closure to first  
plasma

→ Leak detection may take time due to the huge number of flanges on the machine and the number of work performed during shutdown

→ In-vessel water leak: Typical duration 5 weeks



<sup>(1)</sup> May last 3d depending on performed work  
<sup>(2)</sup> May last 2d depending on initial Cryo temp.

# During Campaign: Systems availability



All unavailability are reported in a dedicated database during plasma campaign

Operation downtimes: Time contributions (%) of systems



- Distribution of operation downtimes varies from one campaign to another
- **Analysis of operation downtimes: identification of more frequent failures or delays**

→ Completion of maintenance plan



# **3** ■ **Two Highlights specific to Long Pulse Operation Tokamak**

# Real time protection implemented for Long pulse operation



IR diagnostics (7 endoscopes) installed on the WEST tokamak covering 52% (45m<sup>2</sup>) of the 1<sup>st</sup> wall, 85% of the lower divertor  
IR monitors the surface temperature of critical PFCs in order to prevent damages during long pulses : **definition of Regions Of Interest and associated temperature threshold**

## Two-stage protection


- Limit avoidance: **Real time feedback control acting in a proportional way on the injected power** → only 3% of the feedback controls cross the threshold and lead to triggering an interlock (soft plasma landing)
- Interlock: Identification temperature threshold and deliver an alarm leading to plasma soft landing

First demonstration of inverse IR Neural Network (NN) to **remove reflections and determine accurate surface temperature** from IR images

## Additional diagnostics

- VUV** (Vacuum Ultra Violet) on cooper wavelength: Real time feedback control acting in a proportional way on the injected power
- Calorimetry diagnostic** (~200 sensors & flow meters implemented) with automatic Data processing tool → Thermal Energy

Spatial resolutions from 2mm/px to 0.1mm/px  
temperature uncertainty of 6% at 1000°C



# Actively Cooled Components & Water Leaks management

- Validation of active cooled components before integration in the vacuum vessel
- Specific test: Pressure (45 bars) and temperature (200°C) cycling with helium tightness test



Water leak can occur and involve impact on operation

Tore Supra (24 years): 19 in-vessel water leaks during plasma campaign → ~33 days lost



WEST (2016- )  
7 events

1 week of plasma campaign lost



3 leaks due to design issue  
4 leaks due long operation components

- Leak localisation by pressurization - depressurization of water circuits
- Leak detection by sniffing inside the vacuum vessel
- Leak detection by glow discharge (in progress)

**Leak localization faster and eased by isolation of hydraulic sub-circuits**

→ Improvement of water circuits configuration with the implementation of sets of valves and bottom drains



# Summary & Perspectives


- ❑ WEST is a superconducting long pulse tokamak that involves complex systems (superconducting magnets, cryogenic system, water cooling system, heating systems, power supplies ...)
- ❑ WEST achievements
  - Plasma duration of 364s
  - The WEST availability is > 70% since 2019
  - > 70% of plasma rated as meeting physics program requirements
  - Operation downtimes monitoring is essential to complete the maintenance plan
- ❑ IR Real time protection
  - 52% of the first wall of the vacuum vessel, 85% of the lower divertor monitored by IR diagnostic
  - 97% efficiency of real time feedback control for real time protection
- ❑ Water leak management detection to improve reactivity
  - Typical duration (localization, repair) of an in-vessel water leak: 5 weeks
  - Water network configuration: leak localization faster and eased by isolation of hydraulic sub-circuits

## New capabilities for next campaigns

- Bulk W-tiles (instead of W-coated & BN) on inner and outer start-up limiters
- ECRH, 1 MW available end 2024, 3 MW in 2025
- New diagnostics (Thomson scattering, collector probes, ...)
- Acquisition system compatible with long pulse > 1000s (large flow rate & large amount of data)



irfm



**Thank you for your attention**