

ENGINEERING, CONSTRUCTION, AND FLEXIBLE CONTROL OF MAGNETIC FIELD CONFIGURATION OF QUASI-AXISYMMETRIC STELLARATOR CFQS-T

A. SHIMIZU^{1,2}, M. ISOBE^{1,2,3}, S. OKAMURA¹, K. OGAWA^{1,2}, H. TAKAHASHI^{1,2}, H. YAMAGUCHI^{1,2}, M. SHOJI^{1,2}, M. OSAKABE^{1,2}, L. YANG², T. MURASE¹, S. NAKAGAWA¹, H. TANQUE¹, Y. XU⁴, H.F. LIU⁴, J. CHENG⁴, X. ZHANG⁴, J. HUAN⁴, X. WANG⁴, J.F. SHEN⁴, H. LAN⁴, C. TANG⁵, and D. Yin⁶.

¹ National Institute for Fusion Science, National Institutes of Natural Sciences, Toki, Japan
² The Graduate University for Advanced Studies, SOKENDAI, Toki, Japan
³ Mahasarakham University, Thailand
⁴ Southwest Jiaotong University, Chengdu, China
⁵ Sichuan University, Chengdu, China
⁶ Anhui Link Future Technology Co., Ltd., China

Outline

1. Overview of CFQS quasi-axisymmetric stellarator
2. CFQS engineering
3. CFQS construction
4. Ability of flexible control of CFQS magnetic field configuration
5. Summary

Quasi-axisymmetric configuration of CFQS

The CFQS is designed to combine both advantages of **a stellarator with steady-state operation capability** and **a tokamak with good plasma confinement property**.

Plasma boundary

Fourier spectrum of B in the Boozer coordinates

Magnetic flux surfaces

Magnetic well depth

Rotational transform

A. Shimizu et al., Plasma Fus. Res. **13** (2018) 3403123.

Overview of the CFQS

$B_t = 1$ T, $R = 1$ m, $A_p = 4$ are selected for CFQS to perform proof of principal experiment of QA stellarator concept.

The CFQS plasma experiment is divided into two stages: 1st stage of $B_t < 0.1$ T long pulse operation as "CFQS-T" and 2nd stage of 1 T short pulse operation as "CFQS" after reinforcing the magnetic coil supporting structures.

CFQS-T main body for the 1st stage

No	Parameters	CFQS	W7-X	HSX
1	Configuration type	QA	QI	QH
2	Major radius (m)	1.0	5.5	1.2
3	Minor radius (m)	0.25	0.5	0.15
4	Aspect ratio	4	11	8
5	Magnetic field (T)	1	3	1
6	Toroidal periods	2	5	4
7	Rotational transform	0.35~0.38	0.85~1	1~1.1

- QA : Quasi-axisymmetric
- QI : Quasi-isodynamic
- QH : Quasi-helical symmetric

Components of CFQS-T main body

The CFQS-T main body consists of

- (1) 16 Modular coils,
- (2) 4 sectors of vacuum vessel (VV) with 2 types called VV Type-A, VV Type-B
- (3) Main body supporting structures.

Vacuum vessel and its sector

Assembled VV sectors

Main body support structure

Supporting structure design

1st stage: CFQS-T
0.1 T in Jiuli campus

2nd stage: CFQS
1 T in Tianfu campus

Center pole

The 1st stage machine, i.e., CFQS-T for 0.1 T operation is not equipped with coil cases, full specification of supporting structures, and center pole to withstand electromagnetic force.

Establishment of manufacturing method of MCs

1. Manufacturing of the winding mould
2. Conductor winding
3. 1st VPI for the layer-to-layer insulation
4. Processing of the winding mould for 2nd VPI
5. Ground insulation taping and 2nd VPI
6. Attachment of MC support structures

The inside of mould was cut by 3 mm

After ground insulation taping

Sealed MC for 2nd VPI

After coil legs attachment

- The unique point of MC manufacturing is to adopt vacuum pressure impregnation (VPI) in two steps to maintain the shape of MC winding packs during ground insulation taping without the winding mould.
- All MCs have passed final inspections. They have been manufactured with less than 2 mm dimensional deviation.

Position error of MCs after assembling process

- Dimension measurement of MC position was performed.
- Position error of realized MCs from 3-D CAD design was measured by laser tracker.

The final deviation of MC assembling is -2.96~2.79 mm.

Assembly procedure of the CFQS-T main body

1. Installation of first VV type-A and MCs
2. Installation of the first VV type-B and MCs
3. Installation of second VV type-B and MCs
4. Installation of second VV type-A and main body support structure
5. Installation of the main body in the experimental hall

Pre-assembly of second VV type-A and MC4

Installation of VV type-A and MC4

Maximum position deviation of the MC system including dimensional deviation is achieved to be less than ± 3 mm measured by a laser tracker. It will not significantly affect the magnetic field configuration*. *G. Xiong et al., Plasma Phys. Control. Fusion 65 (2023) 035020.

Installation of CFQS-T into the China-Japan Collaboration Laboratory for Plasma Physics at Southwest Jiaotong University, Chengdu, China

Land transportation from the factory at Hefei and arrival of CFQS-T in July 12th, 2024.

Carrying in

Lifting and moving with a mobile crane

Installation

Unpacking

Overview picture of CFQS-T

- The first plasma of CFQS-T was achieved in August 31st, 2024.
- The CFQS-T campaign was ended in May 2025, and transferred to the factory in Hefei to upgrade to CFQS for 1 T operation.

Magnetic field mapping experiment

Experimental setup for mapping

Fluorescent mesh

2D

3D
 $p \sim 0.067$

$p \sim 0.489$
 $m/n=8/3$

$p \sim 0.740$
 $m/n=11/4$

- The mapping experiment shows the good magnetic surfaces.
- Experiment results match the simulated magnetic surfaces.

A typical plasma discharge in CFQS-T

- The CFQS-T plasma is produced by 2.45 GHz magnetron.
- $P_{ECRH} < 5$ kW.

Control capability for magnetic field configuration

- The rotational transform can be controlled with TFCs, the , by which the divertor configuration can be produced with $m/n = 2/5$ islands structure in the peripheral region.
- Although the QA-ness is slightly deteriorated by this control, effective helical ripple can be kept lower level than that of W7-X.
- By using PFCs, position of the magnetic axis can be shifted.
- By adjusting the current ratio of IV coil to OV coil, rotational transform also can be controlled.

Summary

- The CFQS is a quasi-axisymmetric stellarator having R of 1 m, A_p of 4.
- The CFQS project is performed in two steps, 1st phase: CFQS-T for 0.1 T operation, 2nd phase: CFQS for 1 T operation.
- Construction of CFQS-T was successfully completed in May 2024, and the first plasma was achieved in Aug. 31st 2024.
- Maximum position deviation of the MC system including dimensional deviation is achieved to be less than ± 3 mm measured by a laser tracker. It will not significantly affect the magnetic field configuration
- Magnetic field mapping experiment was performed. Good magnetic surfaces were obtained as we expected, matching the simulation results
- The CFQS for 1 T operation will be started in the end of 2026.