

MACHINE ENHANCEMENT OF TOKAMAK DEVICE FOR THE JT-60SA NEXT OPERATION

H. Kayano, A. Owada, A. Kaminaga, T. Nishiyama, T. Morimoto, K. Fukui, J. Yagyu and Y. Shibama

National Institutes for Quantum Science and Technology (QST), JAPAN

kayano.hiroki@qst.go.jp




Abstract

The largest superconducting tokamak device, JT-60SA, achieved the first plasma successfully in the previous Integrated Commissioning (IC) in 2023. In order to achieve high power plasma heating in the next operation, the Maintenance & Enhancement phase 1 (M/E-1) has been started since January 2024. 18 ports are installed to enable high heating power injection with 3 MW ECRH and 23.5 MW Neutral Beam (NB), and to install the diagnostic system. Cooling water circulation system for in-vessel components is developed. The measures for the issues in previous operation will contribute to robust plasma operation on ITER.

Summary

- The installation of 18 ports and 5 joints has been completed with high accuracy by dedicated jigs and positioning measurement.
- The cooling water circulation system for the in-vessel components is being maintained and enhanced, enduring electrical isolation and displacement absorption of the Vacuum Vessel (VV), the Cryostat, and the stage.
- Gas ballast system, which dilutes condensable gas, will be enhanced to prevent failure of DRy vacuum Pump (DRP).
- The number of Cold Cathode vacuum Gages (CCG) will be increased to improve coil interlock system redundancy and response speed.




Enhancement of the in-vessel component for OP-2

Preparation for the High-Power Heating

Port Installation for High-Power Plasma Heating Operation


- The VV is required to install ports for new equipment such as NBI and diagnostics.
- The NBI system used in the JT-60U are re-used in JT-60SA with the same locations. Owing to clearance with NBI tanks and cryostat, **tolerance of the NBI port is ± 2 mm at its centerline with absolute coordination.**
- Even a small welding distortion can cause major deformation with this large-scale structures (ex. port length: 1.6m).



Port installed

Welding procedure to achieve high precision

- Position measurement: dial gauges and laser trackers.
- Procedure was improved through test, and trial & error.
- Port compartment such as bellows and port pipe are combined as Integrated Port, and installed using dedicated jigs.



18 ports and 5 joints


Installation of all the 18 ports and 5 joints have been completed.
In addition to 55 ports already installed before first plasma, installation of all 73 ports, which is JT-60SA device design, has finely completed.

Cooling Water Circulation System for Long-Pulse Plasma Operation

- In the Operation Phase 2, high heat flux of several seconds will be applied to in-vessel components.
 - e.g., 10 MW m⁻² for 7.5 s and 15 MW m⁻² for 5 s on the lower divertor are planned [1].
- Water circulation system in the JT-60 is maintained for early supply of water-cooling in the JT-60SA.
 - Maintenance of equipment, such as pumps and heat exchanger, is completed.
 - Parts of water piping are being installed.

Enhancement plan of the cooling water circulation system


Research phase	Initial research phase	Integrated research phase
Operation Phase	OP-1	OP-2 to OP-4
Piping	None	Enhanced
Water circulation system	Not maintained	Re-use of JT-60U (~500m ³ /h, ~1.4MPa at pump)
		Enhanced to full specification (~3000m ³ /h, >2MPa)



Schematic drawing of the water circulation system during the Initial Research Phase

- The cooling water is required to pass through three different components; the VV, the Cryostat, and the stage. Each components have different electrical grounding and movement in baking operation and seismic event.

→ **Flexible piping** is designed to absorb displacement of 50 mm in vertical and 10mm in horizontal.



Schematic drawing of water piping pass around tokamak


Water piping (Upper C-ring)

Piping design to satisfy electrical insulation and thermal stress


Improvements in Vacuum Pumping System and Vacuum Interlock System

Improvement in Cryostat Vacuum Pumping System

- Vacuum pumping of the cryostat is carried out under severe conditions, owing to carbon compounds such as polyamide and polyester which constitute multi-layer insulation (MLI).
- In addition, the electrical insulation of the superconducting coil terminal had been reinforced with resin [1].
- Speed of vacuum pumping downed due to outgassing from carbon compounds, brought by the insulation reinforcement.
- Two DRy vacuum Pump (DRP) for cryostat pumping failed during the IC in 2023. One of the cause is damage to the bearings by solidified impurities.
- Impurities are assumed to originate from MLI, machining oil and resin.





Inlet mesh of failed DRP



Solidified impurity materials

Elemental analysis



Energy-dispersive X-ray spectroscopy

Non-condensation condition at compression zone in pump

$$x_{cond} < \frac{p_{cond,sat}(T_{comp})}{p_{comp}}$$

$p_{cond,sat}(T)$: saturation pressure of condensable gas
 p_{comp} : total pressure at compressed zone
 T_{comp} : temperature at compressed zone
 x_{cond} : mole fraction

- To prevent condensation, a gas ballast system will be employed.
 - Inject dry air to decrease the mole ratio of condensable gas before compression.
- Dilution ratio > 10 is assumed.
- Robust operation in the next vacuum pumping




Diagram of the cryostat vacuum pumping and gas ballast system

Vacuum Interlock Gauges for Reliable Superconducting Coil Protection

- Superconducting Coil protective I/L system, that rapidly detects abnormal vacuum degradation and achieve safely termination of the coils, has been constructed from the Operation Phase 1 (OP-1).

Commercial type Cold Cathode vacuum Gauge (CCG)

- used in a relatively low magnetic field environment of Room temperature (called R-CCG).

→ **Aiming at higher reliability**

C-CCG (self-product) [2,3]

- installed on SC coil at cryogenic temperature.


Interlock system response time

- Time of coil current start decreasing after CCG send the setpoint signal.
 - total 73 ms for the EF/CS coil.
 - total about 500 ms for the TF coil.


Test onsite on OP-1

- Controller of the CCG output setpoint signals at 1.41 s after injection of Helium gas about 25 Pa m³.
- C-CCG detect pressure increases about 0.5 s earlier than the R-CCG at the lower space at cryostat.


Improvement for OP-2
Additional 8 R-CCGs will be installed for the faster response and to increase redundancy.



#5~9 Coil terminal box



Sensors and controller of R-CCG installed on port section 02



CCG and setpoint signal at test onsite